

15-167-06350-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 9-8

LOCATION NW NE NW

SEC. 18 TWP. 13 RGE. 14

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease New

Operator Stearns Drg Co Address Russell, Kans

Field _____ County Russell

Total Depth 3202 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 850' circulated with cement. 5 1/2" vat 3198'

with 50 sax cement behind.

Filled with chat to 3190', set 4 sax cement with dump bailer,

pulled 2497' 5 1/2", filled hole with heavy mud to 850', set

rock bridge and 15 sax cement, filled with heavy mud to

40', set rock bridge and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC. 18 T. 13 R. 14
BOOK PAGE 7 LINE 8

E. J. [Signature]
District Conservation Agent

Date 6-2-50

06-05-1950