


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Butler County, Sec. 20 Twp. 25S Rge. 4 (E) E (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner R. J. Wixson et al
Lease Name Whiteside Well No. 1
Office Address El Dorado, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 2nd., 19 54
Application for plugging filed October 29th., 19 58
Application for plugging approved October 30th., 19 58
Plugging commenced November 3rd., 19 58
Plugging completed November 4th., 19 58
Reason for abandonment of well or producing formation
Did not produce sufficient oil
If a producing well is abandoned, date of last production May 15th., 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene H. Graham
Producing formation Chat Depth to top 2512 Bottom 2547 Total Depth of Well 2,547 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	2,516	2,200
				8" Surface	148	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mud from 2,547 to 2,516'
Dumped 3 sacks cement
Dumped 25 sacks cement on 20' rock bridge @ 178'
Filled 8" casing to 45'
Filled to top of 8" with 15 sacks cement.
Filled cellar to top with rock and 10 sacks cement.
Filled to surface with soil

(Certified copy of well log attached)

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1958 12-12-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. H. Wagner Drilling Company
Address El Dorado, Kansas.

STATE OF KANSAS, COUNTY OF BUTLER, ss.
R. J. Wixson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Wixson
El Dorado, Kansas. (Address)

SUBSCRIBED AND SWORN to before me this 7th day of November, 19 58

My commission expires August 14th., 1961.

[Signature]
Notary Public.

PLUGGING
FILE SEC 20 T. 25 R. 4E
BOOK PAGE 140 LINE 35

R. J. WIXSON DRILLING COMPANY

COMPANY R. J. WIXSON ET AL

FARM WHITESIDE NO. 1

TOTAL DEPTH 2547'

COMM. 5-8-54 COMP. 6-2-54

CONTRACTOR: R. J. WIXSON DRILLING CO.

ISSUED: 6-18-54

SEC. 20 TWP. 25 R. 4E

DESC. NE NW NE

COUNTY BUTLER KANSAS

CASING RECORD:

15 1/2"	1140'
13 3/8"	845'
10"	1660'
8"	2230'
7"	2516'

ELEVATION 1306 PRODUCTION 25 BOPD

(FIGURES INDICATE BOTTOM OF FORMATION)

Cellar	8	Red Rock	675	Shale	1570
Clay	15	Shale	680	Lime	1575
Shale	40	Red Rock	685	Shale	1600
Gravel	50	Shale	710	Sandy Shale	1625
	<u>HFW @ 45' - 50'</u>	Shale & Shells	745	Shale	1695
Shale	55	Sand	750	Lime	1700
Lime	70	Shale	770	Shale	1735
Shale	80	Lime	775	Lime	1755
Lime	85	Shale	842	Shale	1793
Shale	100	Lime	845	Lime	1875
Lime	140	Shale	865	Shale	1878
Shale	165	Lime	875	Lime 2 BWPH @ 1900-10'	1940
Lime	175	Shale	880	Shale	2000
Shale	180	Lime	885	Shale	2078
Lime	190	Shale	900	Lime 1 BWPH @ 2140-50'	2180
Shale	195	Lime 1 BWPH @ 920'	945	Shale	2185
Red Rock	200	Shale	950	Lime	2210
Lime	215	Lime	955	Shale	2215
Shale	230	Shale	965	Lime	2240
Lime	240	Lime	975	Shale	2310
Red Rock	250	Shale	1000	Shale & Shells	2350
Lime	275	Lime	1005	Lime	2360
Shale	285	Shale	1055	Shale	2390
Lime	295	Lime Bkn.	1075	Lime Hd	2415
Shale	305	Lime	1080	Shale	2420
Lime	310	Shale	1100	Lime Bkn	2445
Shale	315	Lime	1110	Lime	2460
Lime	335	Shale	1115	Shale	2512
Shale	370	Lime	1120	Chat(Oil from 2539-43')	2547
Lime	375	Shale	1145	Total Depth	2547
Shale	395	Lime	1165		
Red Rock	400	Shale	1175	T/Lans.	1793
Lime	420	Lime 1/2 BWPH @ 1180'	1215	B/Lans.	1940
Shale	425	Shale	1235		
Lime	445	Lime	1260	T/KC	2078
Shale	450	Shale	1270	B/KC	2240
Lime	460	Lime	1285		
Shale & Shells	480	Shale	1290	T/Chat	2512
Lime	500	Lime 1/2 BWPH @ 1295'	1300		
Shale & Shells	515	Shale	1305		
Lime	520	Lime	1325		
Shale	540	Shale	1330		
Lime & Shale	560	Lime	1365		
Shale & Shells	620	Shale	1370		
Shale	645	Lime 3 BWPH @ 1400'	1450		
Lime	650	Shale	1480		
Shale	660	Lime	1520		
Lime	665	Shale	1530		
Red Rock	670	Lime	1555		

STATE OF KANSAS }
COUNTY OF BUTLER } SS

R. J. Wixson of lawful age, being duly sworn on his oath, states that he is the Drilling Contractor or Drilling Superintendent who drilled the well described in the foregoing log, and that the above is a true and correct copy of said log.

Subscribed and sworn to before me this 18th day of June, 1954.

My commission expires Aug. 14, 1957

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 20 T 25 R 4E
BOOK PAGE 140 LINE 35

R. J. Wixson
Notary Public