

15-091-19175-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Johnson County. Sec. 16 Twp. 14 Rge. 22 (E) E (W)

Location as "NE/CNW/SW" or footage from lines C.NW.NW

Lease Owner Gas & Oil Operations

Lease Name Marvin Rankin Well No. 1

Office Address 2018 S. Oliver Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 29 30 19 60

Application for plugging filed August 31 19 60

Application for plugging approved August 31 19 60

Plugging commenced August 31 19 60

Plugging completed August 31 19 60

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D.C. Chickadonz

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 596 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale	Water	30	35	6 1/4	560	560

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 325. Bridged with brush and rock at 325, cemented with 5 sacks. Filled with mud to 150. Bridged with brush and rock at 150, cemented with 5 sacks. Filled with mud to 25. bridged at 25, cemented with 3 sacks. Filled to surface with rock and soil.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ernest Lynn

Address 208 tower Paola, Kansas

STATE OF Kansas, COUNTY OF Miami, ss.

Ernest Lynn (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Ernest Lynn

208 Tower Paola, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of Sept 1960

My commission expires June 29, 1961

Richard D. Okey
Notary Public.



15-091-19175-00-00

Well No. 1

C.NW.NW. 16-14-22E. Johnson County. Marvin Rankin

Thickness of Strata	Formation	Total	Remarks
2	Soil	2	
16	Clay	18	
12	Lime	30	
5	Shale	35	Water
20	Lime	55	
4	Shale	59	
20	Lime	79	
38	Shale	117	
71	Lime	188	
33	Shale	221	
10	Lime	231	
16	Shale	247	
8	Lime	255	
8	Shale	263	
20	Lime	283	
18	Shale	301	
2	Lime	303	
8	Shale	311	
28	Lime	339	
6	Shale	345	
23	Lime	368	
3	Shale	371	
5	Lime	376	
2	Shale	378	
7	Lime	385	Hertha S.L.M.
10	Shale	395	
3	Sand	398	
17	Shale	415	
8	Sand	423	
137	Shale	560	
6	Lime	566	
5	Shale	571	
7	Lime	578	
18	Shale	596	T.D. S.L.M.

RECEIVED
STATE GEOLOGICAL SURVEY
SEP 16 1960
CONSERVATION DIVISION

Well started 8-19-60

Well finished 8-31-60