


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-05661-00-01
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 5 Twp. 11 Rge. 17 (E) (W) X

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Meltzer Oil Company
Lease Name Gumble Well No. X
Office Address 11801 N. Tatum, Phoenix, Az. 85028
Character of Well (completed as Oil, Gas or Dry Hole) SWDW
Date well completed 3/7 1982
Application for plugging filed 7/5 1982
Application for plugging approved State Pluggger gave oral permission 1982
Plugging commenced 7/6 1984
Plugging completed 7/9 1984
Reason for abandonment of well or producing formation SW plugged up the well

If a producing well is abandoned, date of last production -- 19---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Arbuckle Depth to top 3430 Bottom 3440 Total Depth of Well 3530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite	Surface	0	825	8 5/8 "	250 st	0
Arbuckle	Production	3440	3440	5 1/2 "	100 st	0
"	String	3440	3490	4 "	50	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to feet for each plug set.

Had Allied Cement put in 500 sacks of cement, 50-50 posmix and 5 sacks slo-seal, 5 sacks of hulls into well and let set over weekend. Had Allied Cement put measuring line down hole and it stopped at 420 feet. Had cement truck mix 5 yards of redimix (sand and cement) and filled hole to the top and waited two hours. The cement remained at the top. Well plugged.

Dennis Hamel, State Pluggger, was on the site and supervised plugging of the well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Meltzer Oil Company Operator #5202
Address 11801 N. Tatum, Phoenix, Az. 85028

STATE OF Arizona, COUNTY OF Maricopa, ss.
Nathan Meltzer (~~owner or operator~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Nathan Meltzer
(Address) _____

SUBSCRIBED AND SWORN to before me this (TH) day of July, 1984

My Commission Expires Oct. 19, 1987.

Gene Meltzer
Notary Public.

My commission expires _____



RECEIVED
STATE CORPORATION COMMISSION
7-11-1984
JUL 11 1984
CONSERVATION DIVISION
Wichita, Kansas