


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-051-03769-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 5 Twp. 11 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Lee Phillips Oil Company
Lease Name Gumble Well No. 7
Office Address 1407 Union National Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 4 1961
Application for plugging filed May 4 1961
Application for plugging approved May 4 (Verbally) 1961
Plugging commenced May 4 1961
Plugging completed May 4 1961
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Peety
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	910	8 5/8"	910	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 420' with a plug and 20 sacks of cement at this point. Heavy mud to 180' and a plug and 20 sacks of cement at this point. Mud to 40' with a plug and 10 sacks of cement at this point.

RECEIVED
STATE CORPORATION COMMISSION
5-17-1961
MAY 17 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms-Burt Drilling Company
Address P.O. Box 488 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Allan Harms*
P.O. Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of May, 1961
Mary E. Van Pelt
Notary Public.

My commission expires 1-20-62



DRILLERS LOG

Company: Lee Phillips Oil Company
Farm: Gumble # 7
Commenced: April 25, 1961

NW SE SW Section 5-11-17W
Ellis County, Kansas
Completed: May 4, 1961

Elevation: 1899 KB

0 - 250	shale
250 - 435	shale & sand streak
435 - 600	sand
600 - 815	shale
815 - 1000	red bed
1000 - 1150	sand - red bed
1150 - 1190	anhydrite
1190 - 1450	red bed
1450 - 1775	shale & shells
1775 - 2595	shale & lime
2595 - 3052	lime & shale
3052 - 3402	lime
3402 - 3470	conglomerate
3470	Total Depth

Set 910' of 8 5/8" surface pipe. Cemented with 500 sacks of common cement with 2% calcium chloride.

Tops: Anhydrite - 1150
Conglomerate - 3402

Drill Stem Tests: #1 3138 - 3159 Open 1 hour. Shut in 30 minutes.
Recovered 30' oil cut mud, 120' mud cut oil, 60 feet oil cut mud.
IBHP - 1080# FBHP - 775# FFP - 60#

Dry, plugged and abandoned.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms

Subscribed and sworn to before me this 16 day of May, 1961.

Mary E. Van Pelt
Notary Public

My commission expires January 20, 1962.

RECEIVED
STATE CORPORATION COMMISSION
5-17-1961
MAY 17 1961
CONSERVATION DIVISION
Wichita, Kansas