


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-00753-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 5 Twp. 11 Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Mallonee Drilling Company, Inc.
Lease Name Carmichael Well No. 1
Office Address 820 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-9 19 58
Application for plugging filed 9-9 19 58
Application for plugging approved 9-9 19 58
Plugging commenced 9-9 19 58
Plugging completed 9-9 19 58
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	254	8-5/8	254	None - cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 435', 20 sacks cement.
Plug set at 180', 20 sacks cement.
Plug set at 40', cement and hulls to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 820 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. Mallonee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
820 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 19 58

My commission expires December 14, 1961

[Signature]
Notary Public.

PLUGGING
FILE SEC. 5 T. 11 R. 17W
BOOK PAGE 130 LINE 11

9-17-1958
SEP 17 1958
CONSERVATION DIVISION
KANSAS

DRILLERS' LOG

#1 Carmichael
 SW SW SE Section 5-115-17W
 Ellis County, Kansas

OPERATOR: Mallonee Drilling Company, Inc.
 CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: 8-27-58
 COMPLETED: 9-9-58

FROM	TO	DESCRIPTION
0	100	Clay, sand and shells
100	480	Shale and shells
480	555	Shale and sand
555	610	Sand and iron
610	687	Sand and shells
687	840	Sand
840	1130	Red bed and shells
1130	1165	Anhydrite
1165	1380	Shale and shells
1380	1480	Shale, shells and salt
1480	1575	Shale and shells
1575	1740	Lime and shale
1740	1945	Shale and shells
1945	3115	Lime and shale
3115	3340	Lime
3340	3372	Lime and shale
3372	3423	Lime, shale and chert
3423	3459	Lime and shale
3459	3500	Lime
3500		Rotary Total Depth

CASING RECORD

8-5/8" surface casing set at 254' with 150 sacks Pozmix, 1 CC. Cement circulated.

Drill Stem Test #1, 3452 - 3459
 Open 1 hour, recovered 780' oil, 1140' sulphur water. BHP 1020#

Elevation: 1889 KB

Tops:		
Heebner	3066	-1177
Toronto	3089	-1200
Lansing	3108	-1219
Base K.C.	3345	-1456
Conglomerate	3381	-1492
Simpson shale	3418	-1529
Simpson dolomite	3436	-1542
Simpson sand	3446	-1557
Arbuckle	3450	-1561
R.T.D.	3500	-1611

Geologist: Stephen B. Powell

I hereby certify that to the best of my knowledge and belief, the above represents a true and accurate Drillers' Log of the captioned well.

R. E. Mallonee
 R. E. Mallonee

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 16th day of September, 1958.

My commission expires:
 December 14, 1961

Martha Gorges
 Notary Public (Martha Gorges)

RECEIVED
 CORPORATION COMMISSION

PLUGGING SEP 17 1958
 FILE SEC 5 T. 11 R. 17W
 BOOK PAGE 130 LINE 11

DIVISION