



WELL LOG

Petroleum, Inc.  
McCarroll #1

NE NE & S/2 NE,  
Sec. 6, 11S-17W  
County: Ellis

Total Depth: 3535'  
Comm: 1/27/49 Comp: 2/15/49  
Contractor: Petroleum, Inc.  
Rotary: 0-3535'

Elevation: 1957' DF  
Production: Dry

Casing: 209' 8 5/8" 28#, cemented with 125  
sacks; Halliburton Cement circulated.

Figures indicate bottoms of Formations:

|                      |      |          |      |
|----------------------|------|----------|------|
| surface rock & shale | 100  |          |      |
| shale                | 130  | TOPS:    |      |
| shale & shell        | 400  | Topeka   | 2921 |
| red bed              | 470  | Heebner  | 3147 |
| shale                | 710  | Dodge    | 3168 |
| sand                 | 890  | Lansing  | 3190 |
| red bed              | 1190 | Arbuckle | 3532 |
| Anhydrite            | 1250 |          |      |
| shale & shell        | 1300 |          |      |
| shale                | 1790 |          |      |
| lime & shale         | 1845 |          |      |
| lime & shale         | 1880 |          |      |
| shale                | 2030 |          |      |
| shale & lime         | 2050 |          |      |
| lime                 | 2210 |          |      |
| shale                | 2290 |          |      |
| lime & shale         | 2495 |          |      |
| shale                | 2620 |          |      |
| lime & shale         | 3152 |          |      |
| lime                 | 3350 |          |      |
| lime & shale         | 3415 |          |      |
| lime                 | 3485 |          |      |
| chert & lime         | 3493 |          |      |
| lime & shale         | 3516 |          |      |
| shale                | 3535 |          |      |

RECEIVED  
Conservation Dept.  
2-21-1949  
FEB 21 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

PLUGGING RECORD

Mixed heavy mud and circulated.  
Placed wooden plug at 206'.  
Mixed and dumped 20 sacks cement on top plug.  
Finished filling hole with heavy mud and placed 5 sacks cement  
in top of surface casing.

We hereby certify this to be a correct and accurate log of the  
above described well, as shown on the daily drilling reports.

PETROLEUM, INC.

BY: Charles M. Seale

Subscribed and sworn to before me this 19<sup>th</sup> day of February,  
1949.

Marjorie Bradshaw  
Notary Public

My commission expires:  
October 27, 1952.



**PLUGGING**  
FILE SEC 6-T-11-R-17W  
BOOK PAGE 83 LINE 17