

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

15-051-03290-00-00

LEASE NAME HENDERSON

TYPE OR PRINT

WELL NUMBER B#2

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SPOT LOCATION C W/2 SW SW

SEC. 6 TWP 11S RGE 17W (E) (W)

LEASE OPERATOR KELSO CASING PULLING (Bought from
Box 347 Energy Reserve Group, Inc.) COUNTY Ellis
ADDRESS Chase, Kansas 67524

Date Well Completed _____

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Plugging Commenced 5-18-84

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-25-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3499'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10"	1223'	none
				7"	3494'	308'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

(Junk in hole) 2-7/8" 10rd. Tubing wih piece of collar looking up. Top @ 3055.00'.
Ran 14 sacks of cement on top. Took stretch and 1/2" casing was into. Pulled 11 joints.
Plugged surface with 4 hulls, 25 cement, 15 gel, 70 cement, 5 gel, 1 hull, plug and
70 cement. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

JUN 06 1984
6-6-1984

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19__

IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
NOTARY PUBLIC

My Commission expires _____

15-051-03290-00-00
 THE DICKEY OIL COMPANY
 HENDERSON-B #2

COMMENCED: 4/21/40
 COMPLETED: 5/14/40

LOCATION: C-W/2 SW/4 SW/4
 6-11-17 Ellis Co., Kans.

Pipe Record

	15 1/2"
1223'	10 "
3487'	7 "

shale and shells	710
sand	865
red bed	1205
top of anhydrite	1205
anhydrite	1250
shale and red bed	1355
shale and shells	1525
salt	1630
shale and shells	1772
shale	1785
broken lime	2194
lime	2280
shale and shells	2400
broken lime	2448
shale and shells	2762
shale and lime	2845
shale	2896
top of Topeka lime	2896
lime	3190
red bed	3200
shale and lime	3220
top of K. C. lime	3220
lime	3400
broken lime	3445
conglomerate	3460
dolomite	3476
green shale	3487
top of siliceous	3487
siliceous lime	3488
T. D.	3493

RECEIVED
 STATE CORPORATION COMMISSION
 5-2-1984
 MAY 02 1984

CONSERVATION DIVISION
 Wichita, Kansas