

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-05663-00-00  
WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 11S Rge. (E) 17 (W)

NORTH R17W

	6		
		0#2	

Locate well correctly on above  
Section Plat

Location as "NE/CNWxSWx" or footage from lines N/2 SW SE  
Lease Owner Pan American Petroleum Corporation  
Lease Name K. Gumble Well No. 2  
Office Address Box 1654, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 12-22-1940  
Application for plugging filed 8-15-1963  
Application for plugging approved 8-16-1963  
Plugging commenced 9-12-1963  
Plugging completed 9-16-1963  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production April 1963  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top 3445 Bottom 3447 Total Depth of Well 3447 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Depleted	3445	3447	10"	1152	None
				7"	3446	Unknown

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3447 feet to surface feet for each plug set.

Bottom had been plugged off - dumped 3 sacks of cement on plug - shot off pipe and pulled pipe up to 550' - circulated with mud - pulled pipe up to 490' - spotted 20 sacks of cement - pulled pipe out of hole - dumped 10 sacks of cement on top. Cement came to bottom of cellar - plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION  
10-1-1963  
OCT 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnes & Sons Pipe Pulling Company  
Address P. O. Box 313, Russell, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
G. A. Reynolds (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. A. Reynolds Area Supt.

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1963

My commission expires January 9, 1965

Earle J. Thompson  
Notary Public.

R

15-051-05663-00-00

THE DICKEY OIL COMPANY  
Gumble #2

COMMENCED: 11-30-40  
COMPLETED: 12-22-40

LOCATION: C/NE 1/4 SW 1/4 SE 1/4 6-11-17  
Ellis County, Kansas  
ELEVATION:

Pipe Record

1152'  
3445'6"

10"  
7"

Shale	145
Shale and Shells	595
Iron	605
Shale and Shells	700
Sand	810
Red Bed	1143
Anhydrite	1188
Shale and Shells	1460
Salt and Shale	1638
Salt	1665
Shale and Shells	1750
Broken Lime	2120
Lime	2195
Broken Lime	2273
Shale and Shells	2351
Broken Lime	2404
Shale and Shells	2716
Broken Lime	2750
Shale and Shells	2885
Top Topeka	2885
Lime	3148
Top K. C. Lime	3148
Oil Show	3150-3153
Lime	3349
Broken Lime	3380
Conglomerate	3419
Simpson Dolomite	3425
Green Shale	3444
Simpson Sand	3445 1/2
Top Arbuckle	3445 1/2 D.F.
Lime	3447 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
10-1-1963  
OCT 1 1963  
CONSERVATION DIVISION  
Wichita, Kansas

CORRECTION:

Conglomerate	3417 1/2
Simpson Dolomite	3423 1/2
Green Shale	3442 1/2
Simpson Sand	3445 1/2
Top Arbuckle	3445 1/2
Arbuckle	3447 T.D.