

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

15-051-02095-00-01
API NUMBER Compl 7/48

LEASE NAME Gumble

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely

330 Ft. from S Section Line

and return to Cons. Div.

330 Ft. from E Section Line

office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC. 6 TWP. 11 S RGE. 17W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY Ellis

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 7/48

Character of Well SWD (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 12/15/97

Plugging Completed 12/16/97

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation ARB Depth to Top 3490 Bottom 3745 TD 3745

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put	Pulled out
				8 5/8	1132	
				5 1/2	3437	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran tbg to 1875', tag up, solid btm. Pumped 65 sx 60/40 Poz w/300# hulls. Fill up 1875' to 800'. Pulled tbg to 900', pump

65 sx 60/40 Poz w/200# hulls. Cmt circ to surface. TOH w/tbg. Hook up to 5 1/2", pump 20 sx 60/40 Poz, press 1200#, SI 1000#.

Hook up to surface pipe, pump 25 sx 60/40 Poz w/20# hulls. Press to 500# SI.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Larry M. Jack
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 18 day of December, 1997

9h : 1
1997 DEC 19
12-19-1997
KANSAS CORP COM

(My Commission Expires: 2/6/98)

Kerran Redington
Notary Public - Kerran Redington



Form CP-4
Revised 05-88