

API NUMBER 15-035-22,438 -

LEASE NAME Hosetter

WELL NUMBER #7

Ft. from S Section Line

NE SE SW
Ft. from E Section Line

SEC. 22 TWP. 33 RGE. 4 (E) or (W)

COUNTY Cowley

Date Well Completed _____

Plugging Commenced 7-26-88

Plugging Completed 7-27-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Camio Oil Co.

ADDRESS 16046 E. Harey Wichita, KS. 67230

PHONE (316) 733-5141 OPERATORS LICENSE NO. 6723

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist #2

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation _____ Depth to Top 3134 Bottom 3140 T.D. 3190

Show depth of _____ all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put In	Pulled out
<u>AUG 10 1988</u>			<u>8 5/8"</u>	<u>210'</u>	<u>0</u>
			<u>4 1/2"</u>	<u>3189'</u>	<u>2017'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Fill with chat to 3080' Dup 4SX Cement
Sheet 155 @ 2017' by C. J. Don
Set R.B. 300' to 275' w/ 5 yds. Red. M.C.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B+S Well Service Inc. License No. 6013


Address Box 837 Winfield, KS 67156

STATE OF KS. COUNTY OF Cowley, ss.

DALE Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Winfield, KS. 67156



SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 88

Wayneva C. Leftwich
Notary Public

My Commission Expires: February 29, 1992

DRILLERS LOG

OPERATOR: Camio Oil Co.; Box 153; Augusta, Ks. 67010

CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**

Lease Name Hostetler Well No. 7

Sec. 22 T. 33 R. 4E Spot _____

County Cowley State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 210' with 190 Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Total Depth 3190' KB

Drilling Commenced: 1/30/80 Drilling Completed 2/4/80

Formation	From	To	Tops
Cellar	0	7	Layton - 2443
Shale, Lime	7	915	Kansas City - 2612
Shale	915	1085	Mississippi - 3134
Lime, Shale	1085	1825	
Shale	1825	1973	
Lime	1973	1979	
Shale	1979	2008	
Sand, Shale	2008	2120	
Shale	2120	2393	
Shale, Lime	2393	2443	
Sand	2443	2580	
Shale	2580	2612	
Lime	2612	2730	
Shale	2730	2795	
Lime	2795	2932	
Shale	2932	3134	
Lime	3134	3190	

RECEIVED
STATE CONSERVATION COMMISSION
JUN 24 1988
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots