

API NUMBER 15-035-22520 -

LEASE NAME Hosettee 0000

WELL NUMBER #9

NE, NE NW
Ft. from S Section Line

Ft. from E Section Line

SEC. 22 TWP. 33 RGE. 4 (B) or (W)

COUNTY Cowley

Date Well Completed _____

Plugging Commenced 7-21-88

Plugging Completed 7-22-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Camio Oil Co.

ADDRESS 16046 E. Harry - Wichita, KS 67280

PHONE (316) 733-8131 OPERATORS LICENSE NO. 6723

Character of Well oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #2

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 3156' Bottom 3162' T.D. 3214'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8"</u>	<u>226'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>3213'</u>	<u>2000'</u>

RWD
00-28-88

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Fill w/chart to 3100' Dumps/ Sr Cement
Shoot & Recover 2000' of CSG. Rock Bridge 300' to 275'
5 yds. P.D. Mu

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B+S Well Service Inc. License No. 6013

Address Box 837 Wintfield, Ks.

STATE OF KANSAS COUNTY OF Cowley, ss.


Dale Smith

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. [Signature]

(Address) Wintfield, Ks.



SUBSCRIBED AND SWORN to before me this 26th day of July, 19 88

Wayneva C. Leftwich
Notary Public

My Commission Expires: February 29, 1992

DRILLERS LOG

MIKE HAYDEN
KEITH R. HEN
RICH KOV
MARGA

OPERATOR: Camio Oil Co.; Box 153; Augusta, Ks. 67010

CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**

Lease Name _____ Hostetter _____ Well No. _____ 9

Sec. _____ 22 _____ T. _____ 32 _____ R. _____ 4E _____ Spot _____

County _____ Cowley _____ State _____ Kansas _____ Elevation _____

Casing Record:

Surface: 8 5/8" @ 226.20' with 100 Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: _____ Oil _____ Total Depth _____ 3215' KB _____ 3210 TD

Drilling Commenced: _____ 5/4/80 _____ Drilling Completed _____ 5/8/80 _____

Formation	From	To	Tops
Cellar	0	7	Layton - 2456
Lime, Shale	7	1680	Mississippi - 3154
Shale	1680	2005	
Sand	2005	2123	
Shale	2123	2456	
Sand	2456	2470	
Shale, Lime	2470	2656	
Lime	2656	2740	
Shale, Lime	2740	2935	
Shale	2935	3154	
Lime	3154	3215	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots