

6 070159

API NUMBER 15-167-22,357-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE-SE-SE, SEC. 36, T. 12 S, R. 13 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

900 feet from N() section line
330 feet from W() section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5738
Operator: CRUDE PRODUCERS INC.
Name & Address: BOX 55
RUSSELL, KANS.
67665

Lease Name SHAFFER Well # 1
County RUSSELL
Well Total Depth 3375 109.69 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated Tag # 796

Plugging Contractor REVLIN DRUG. INC License Number 5671

Address ~~4-3~~ BOX 293 - RUSSELL, KANSAS 67665

Company to plug at: Hour: 4:10 AM Day: 1st Month: JUNE Year: 19 84

Plugging proposal received from DUANE POPP

(company name) REVLIN DRUG. INC (phone) 913-483-4371

were: 8 5/8" - 423 FT SP. CUL. w/ 225' SK CNT COMMON

ORDER 175 SK 50/50 Pozmix 4 1/2% 3% GEL - CA-CL - 1 SK 710 GEL AND 8 5/8" PLUG

NO CIRCULATION PROBLEMS, ELEV. 1869. - ANH 803, NO ARBUCKLE

SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

Plugging Proposal Received by Marion Schmidt
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:30 AM Day: 1st Month: JUNE Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 175 SK 50/50 POZMIX 4 1/2% 3% GEL - CA-CL - 1 SK 710 GEL + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 810 FT w/ 25' SK CNT. - 2nd Plug @ 570 FT w/ 80' SK CNT.

AND w/ 1 1/2" SK Cello Flare, 3rd Plug @ 248 FT w/ 50' SK CNT

4th Plug ^{SOLID BRIDGE} HULLS- PLUG @ 40 FT w/ 10' SK CNT, 10' SK IN RAT HOLE

(CIRCULATE) Cemented by Allied CNT

Remarks: RECEIVED
STATE CORPORATION COMMISSION (If a permit is necessary, use BACK of this form.)

INVOICED

DATE 6-14-84 (did not) 6-11-1984 plugging.

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 2014
6-1 JUL 17 1984

Signed Marion Schmidt
(TECHNICIAN) BOIC