

1 080453

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,608-00-00

C SW SW SE, SEC. 33, T 28 S, R 15 W/4

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Moore Well # 1

Operator: Vac Petroleum

County Pratt 157-98

Name & Address Rt. # 1, Lake Road

Well Total Depth 4861 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 422

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:45 pm Day: 25 Month: November Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4860' PBD 4820' Perfs at 4552-62'; 4524-36'; 4484-94'; Top of cement 3900'
4727-37'; 4721-24'; 4705-12'; 4793-98'

1st plug pump 50 sx cement and stop plug at 4400'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 pm Day: 25 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 50 sx cement and stopped
plug at 4400', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx
gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

Maximum pressure 600 psi and shut in 50 psi

Remarks: Recovered 3181' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1985

INV. NO. 11381

RECEIVED
STATE CORPORATION COMMISSION

Signed DEC 5 1985

J. N. [Signature]
(TECHNICIAN)