

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ADW

SW-NE-SW Sec. 35, T 11 S, R 16 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6261

Lease Name Christer Well # 1

Operator: Ernst & Steink Oil Oper.
Name & Address Russell, Kansas

County Ellis

Well Total Depth 3420 feet 111.15'

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 277' w/165' ex

67665

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sun Cementing Co License Number _____

Address Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 24 Month: 1 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Richard Steink

(company name) Ernst & Steink (phone) _____

were: 8 5/8" set @ 277' w/165' ex; 4 1/2" set @ 3419' w/200' ex

Top perf. @ 2975' - P.B. w/sand to 3270' -> 5' ex cmt ->

sand to 2975' & 5' ex cmt. - Shots 1 - Recovered 2220' of csg.

Ordered 190 sy ^{50'} 50' per 6% gel, 18 sy. gel, 6 sy hulla
& 8 5/8" W. Plug

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 A.M. Day: 24 Month: 1 Year: 19 84

ACTUAL PLUGGING REPORT

Logd in 8 5/8" S.P. -> 4 sy hulla -> 18 sy gel ->

Rel. W. Plug -> 190 sy cmt w/2 hulla

May P.S.I. - 500 #

Shut-in P.S.I. 300 #

Remarks: Cmt by Sun

I hereby certify that the above plugging instructions were given as herein stated and that I (did/ did not) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION

Signed Dennis L. Hamel
(TECHNICIAN)

DATE 1-31-84 1-30-1984
JAN 30 1984

FORM CP-2/3
Rev. 9-82

INV. NO. 9293 W
CONSERVATION DIVISION
Wichita, Kansas

1-24