

10-17

4-060595

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-20,740-00-00

SW SW NW /4 SEC. 03 , 13 S, 14 W  
2970 feet from S section line  
4950 feet from E section line

Operator license# 7054

Lease Clausen "B" well # 1

Operator: Doonan & Sons, Inc.

County Russell

Address: P.O. Box 1286  
Great Bend, Kansas 67530

Well total depth 3030 feet <sup>98.47</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 634 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Mike's Pipe Testing & Salvage, Inc. License 31529

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 10:30A.M Day: 17 Month: October Year: 94

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Pipe Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 190 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.  
"Black Magic" mixture in casing annulus outside of 4 1/2".

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 3:00P.M., Day: 17, Month: October, Year: 94

Actual plugging report: 8 5/8" to 634' w/325 sxs. 4 1/2" to 3029'.  
Sanded to 2770' and spotted 4 sxs. cement with dump bailer. Shot casing  
loose at 1400'. Mixed and pumped 65 sxs. cement with 200# hulls.  
Pulled casing to 675' and circulated cement to surface with 90 sxs. cement  
with 100# hulls. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation: 1589 GL

I did [ X ] / did not [     ] observe the plugging.

*[Signature]*  
10-27-1994  
(agent)  
Form CP-2/3

DATE 11-2-94  
INV. NO. 41558