

6010169

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22413-00-00

NE, SEC. 1, T. 13 S, R. 14 W
3960 feet from N/W section line of SE cor.
2310 feet from W/W section line of SE cor.

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Boxberger Well # 1

Operator: Damar Res. Inc.

County Russell

Name & Address Box 70

Well Total Depth 2935 95.39 feet

Hays Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 377

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Emphasis License Number 8241

Address Russell Ks.

Company to plug at: Hour: AM Day: 8 Month: 7 Year: 19 84

Plugging proposal received from Greg Flax

(company name) Emphasis (phone) 913-483-5345

were: order 160 sx. cement 50/50 portmix 6% Gel 3% c.c.
1 sx. hulls 1-8 5/8 plug

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1683 Anhydrite 646-80 Arbuckle etc.

Dakota. 1600 Plugging Proposal Received by Paul F. Balthazor
83-380 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None (circled)

Operations Completed: Hour: 3:30 PM Day: 8 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 680 for 10 mi.

100 sx @ 680

40 sx @ 200 Dumped 15x hulls pushed plug to 40'

10 sx @ 40

10 sx in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1984

07-16-1984
CONSERVATION DIVISION

Remarks: Cementing to sun
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed Paul F. Balthazor
(TECHNICIAN)

DATE 7-24-84

INV. NO. 2612

July 13/84
10