

4-050248

15-051-2440-00-00  
API Number: 15-051-24,440

9-27

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW NW NW /4 SEC. 02, 11 S, 17 W  
4290 feet from S section line  
4950 feet from E section line

Operator license# 30762 Lease: Anderson Well # 1

Operator: Oil Company of America, Inc. County: Ellis 112.02

Address: 1200 Main - Suite #406 Well total depth 3447 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
913-625-3800 Surface pipe 8 5/8 Inch @ 1072 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike Kelso License#

Address:

Company to plug at: Hour: A.M. Day: 27 Month: September Year: 1996

Plugging proposal received from: Darrell Herl

Company: Oil Company of America, Inc. Phone: 913-625-3800

Were: Order 260 sxs 60/40 pozmix - 10% gel - 300# hulls.  
Elevation 1848' - 8 5/8" set at 1072' - 5 1/2" set at 3447'. Perfs at 2976' - 3250' - Dakota  
223' - 500' - Anhydrite 1068' - 1103' - Salt 1368' - 1642'. Sanded back to 2925' with 5 sxs.  
Recovered 1950' 5 1/2" casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour 7:00P.M., Day: 27, Month: September, Year: 1996

Actual plugging report: Pulled casing to 1650' - pumped 115 sxs cement and 300# hulls.  
Pulled casing to 1100' - pumped 40 sxs cement. Pulled casing to 550' - pumped 105 sxs cement  
circulated. Pulled rest of casing.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 1848 GL

I did [ X ] / did not [ ] observe the plugging.

Marvin Miller  
(agent)

DATE 10-7-96

INV. NO. 46657