

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-23242-00-00

API NUMBER 15-051-23,242

LEASE NAME Chrisler

WELL NUMBER 2

SPOT LOCATION NE SW SW

SEC. 11 TWP. 11 SRGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 12/14/82

Plugging Commenced 12/04/84

Plugging Completed 12/06/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 E. 30th, Suite A, Hays, Ks. 67601

PHONE # (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dist. #6 @ 1014 Cody, Hays, Ks. 67601

Is ACO-1 filed? previously If not, is well log attached? was attached to Form CP-1

Producing formation K.C. & Arbuckle Depth to top 2920' bottom 3342' T.O. 3342'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	water	150	550	8 5/8"	256'	
Cedar Hill	water	635	900	5 1/2"	3472'	1830'
L.K.C.	water w/trace oil	2995	3320			
Arbuckle	water w/trace oil	3342	3410			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Squeezed off all zones from 2860 to 3352'-T.D. with 250 sacks cement pumped down 8 5/8" with 4 hull; 25 cement; 15 gel; 70 cement; 5 gel; 1 hulls; 8 5/8" plug and 70 sacks cement to 5' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Superior Well Service License No. 7733

Address Junction K-18, Box 276, Plainville, Ks. 67663

STATE OF Kansas COUNTY OF Ellis, ss.

LeRoy Berland

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) LeRoy Berland

(Address) 400 S.W. 6th Plainville, Ks.

SUBSCRIBED AND SWORN TO before me this day of , 19

My Commission expires:

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
2-4-1985
FEB 04 1985
CONSERVATION DIVISION
Wichita, Kansas