

15-051-0238-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Spudded 9-13-54
LEASE NAME McCombs
WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line
3630 Ft. from E Section Line
SEC. 11 TWP. 11 RGE. 17 (E) or W
COUNTY Ellis

LEASE OPERATOR Palomino Petroleum, Inc.
ADDRESS 4924 SE 84th Street, Newton, Kansas 67114-8827
PHONE# (316) 283-0232 OPERATORS LICENSE NO. 30742

Date Well Completed 9-22-54
Plugging Commenced 11-25-94
Plugging Completed 11-25-94

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 25, 1994 (date)
by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Spudded 9-13-54 If not, is well log attached? Yes
Producing Formation L-KC Depth to Top 2939 Bottom 3366 T.D. 3370

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	1031	8 5/8		0
	Production	0	3370	5 1/2		1800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran the bailer and found T.D. at 2850'. Mixed 5 sacks of cement and dumped with the bailer. Rigged up L-K and ran free point and cut 5 1/2" at 1800'. Pulled a total of 55 joints of 5 1/2"-14#. Spotted 150 sacks of 60/40 - 10% gel; 300# hulls at 1750'; 25 sacks at 1100'; 75 sacks at 650' and filled the top with 10 sacks.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. none required
Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.
STATE OF KANSAS COUNTY OF HARVEY, ss.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1994

Klee R. Watchous, President of Palomino Petroleum, Inc. (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as entered on the same are true and correct, so help me God.

(Signature) Klee R. Watchous
(Address) 4924 SE 84th Street
Newton, Kansas 67114-8827

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1994

KATHRYN L. FRERKING
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 8-31-97

Kathryn L. Frerking
Notary Public

Commission Expires: August 21, 1997