

RECEIVED

AUG 04 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA Type or Print on this Form Form must be Signed All blanks must be Filled

Form CP-4 March 2009

OPERATOR: License #: 5259 Name: Mai Oil Operations, Inc. Address 1: 8411 Preston Road, Suite 800 City: Dallas State: TX Zip: 75225 + 5520 Contact Person: Allen Bangert Phone: (214) 219-8883 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 009-25451-00-00 Spot Description: NW SE SE SE Sec. 15 Twp. 17 S. R. 15 East West 340 Feet from North South Line of Section 400 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: McMullen-Helfrich Well #: 2 Date Well Completed: D & A The plugging proposal was approved on: 07-28-10 (Date) by: Bruce Rodie (KCC District Agent's Name) Plugging Commenced: 07-29-10 Plugging Completed: 07-29-10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8" new 23#, 957', 0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug well with 205 sacks of 60/40 Poz, 4% gel, 1/4# floseal per sack. 1st plug @ 3502' with 25 sacks. 2nd plug @ 1010' with 40 sacks. 3rd plug @ 475' with 100 sacks. 4th plug @ 40' with 10 sacks to surface. Plug rat hole with 30 sacks. Job complete @ 9:15 a.m. on 07-29-10 by Allied Cement (tkr #041573).

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc. Address 1: PO Box 276 Address 2: 8 North Main City: Ellinwood State: KS Zip: 67526 Phone: (620) 564-3800 Name of Party Responsible for Plugging Fees: Mai Oil Operations, Inc.

State of Kansas County, Barton, ss. Renee Kasselmann, Office Manager for Southwind Drilling, Inc. Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Renee Kasselmann 08-03-10

**SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS**

Lease: McMullen - Heiflich #2

Plugging received from KCC representative:

Name: Bruce Rodie Date 7-28-10 Time 1:30 P.M.

1st plug @ 3502 ft. 25 sx. Stands: 56 1/2

2nd plug @ 1010 ft. 40 sx. Stands: 16 1/2

3rd plug @ 475 ft. 100 sx. Stands: 7 1/2

4th plug @ 40 ft. 10 sx. Stands: 1

5th plug @ _____ ft. _____ sx. Stands: _____

Mousehole _____ sx.

Rahole 30 sx.

Total Cement used: 205 sx.

Type of cement 6 3/4 Poz. 4% Gel 1/4" flo seal

Plug down @ 9:15 A.M. 7-29-10

Call KCC When Completed:

Name: Matvin Mills Date 7-29-10 Time 11:30

RECEIVED
AUG 04 2010

KCC WICHITA

