

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30717  
Name: Downing-Nelson Oil Co. Inc.  
Address 1: P.O. Box 372  
Address 2: \_\_\_\_\_  
City: Hays State: Ks. Zip: 67601 + \_\_\_\_\_  
Contact Person: Terry W. Piesker  
Phone: ( 785 ) 735-4363  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3816" Bottom: 3832' T.D. 3892  
Topeka Depth to Top: 3208" Bottom: 3217' T.D. \_\_\_\_\_  
L-KC Depth to Top: 3506" Bottom: 3696' T.D. \_\_\_\_\_

API No. 15 - 195-22,533-00-00  
Spot Description: 60' S and 60' W  
- - SE SW Sec. 12 Twp. 13 S. R. 21  East  West  
600 Feet from  North /  South Line of Section  
2,040 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Trego  
Lease Name: Eger Well #: 7  
Date Well Completed: 3-11-08  
The plugging proposal was approved on: 7-28-10 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 8-2-10  
Plugging Completed: 8-2-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	Oil and water	Surface	8 5/8"	212'	none
Topeka	Oil and water	Long String	5 1/2"	3915'	
L-KC	Oil and water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 75 sxs. 60/40 Poz, 4% Gel with 300# Hulls and followed with 16 sxs. Gel and 147.5 sxs. of 60/40 Poz, 4% Gel with 300# Hulls. Pressured to 1000# SIP- 500# and held solid. Tied to backside and mixed 12.5 sxs. 60/40 Poz and pressured to 200#. Job Complete.

Plugging Contractor License #: \_\_\_\_\_ Name: Quality Oilwell Cementing, Inc.  
Address 1: P.O. Box 32 Address 2: \_\_\_\_\_  
City: Russell State: Kansas Zip: 67665 + 0032  
Phone: ( 785 ) 483-2025

Name of Party Responsible for Plugging Fees: Downing-Nelson Oil Co. Inc.  
State of Kansas County, Ellis, ss.  
Terry W. Piesker  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
AUG 04 2010  
KCC WICHITA