

RECEIVED

AUG 03 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA Type or Print on this Form Form must be Signed All blanks must be Filled

Form CP-4 March 2009

OPERATOR: License #: 32278 Name: Tengasco, Inc. Address 1: P.O. Box 458 City: Hays State: KS Zip: 67601 Contact Person: Gary Wagner Phone: (785) 625-6374 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: D-26,646 ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet)

API No. 15 - 009-24,513 -00-00 Spot Description: NE SW NW Sec. 30 Twp. 20 S. R. 15 East West 1,650 Feet from North South Line of Section 990 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: Unruh Well #: 4 Date Well Completed: The plugging proposal was approved on: 07/16/10 (Date) by: Bruce Rodie (KCC District Agent's Name) Plugging Commenced: 07/20/10 Plugging Completed: 07/21/10

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface, Conductor & Production). Sub-columns include Formation, Content, Casing, Size, Setting Depth, and Pulled Out.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

07/20/10 - Drive rig to location. Sand well back to 3880'. Rig up. Spot 5 sacks cement on top of sand. Set casing jacks. Could not get slips out of Braiden head. Rack out jacks. Shut down for day. 07/21/10 - Drive to location. Wait on Log-Tech. Perforate at 1600', 1150', 700' and 150'. Unload 57 jts of 2-3/8" tubing. Run 1600' of tubing. 1st plug @ 1600' w/40 sacks 60/40 - 4% gel w/200# hulls. 2nd plug @ 1150' w/50 sacks 60/40 - 4% gel w/100# hulls. 3rd plug circulate to surface w/105 sacks 60/40 - 4% gel. Pump 10 sacks down back side. Clean tools. Rig down and clean location.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc. Address 1: 1822 24th Street Address 2: City: Great Bend State: KS Zip: 67530 + 2623 Phone: (620) 793-5838

Name of Party Responsible for Plugging Fees: Tengasco, Inc. State of Kansas County, Barton, ss.

Tim Dickson (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson