

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5278
Name: EOG Resources, Inc.
Address 1: 3817 NW Expressway ; Suite 500
Address 2: _____
City: Oklahoma City State: OK Zip: 73112 + 1483
Contact Person: Candy Driscoll
Phone: (405) 246-3140
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 6890' Bottom: 7807' T.D. 8000'MD
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-22074-01-00
Spot Description: _____
N2 SE SE NW Sec. 714 Twp. 34 S. R. 34 East West
2,220 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Charles Well #: 14 # 1H
Date Well Completed: 2/28/2007
The plugging proposal was approved on: 8/4/2010 (Date)
by: Steve Pfifer (KCC District Agent's Name)
Plugging Commenced: 8/4/2010
Plugging Completed: 8/6/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
6890-7807'	gas, water	Surface	9 5/8"	1684'	None
		Production	4 1/2"	7992'	2695'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg set 4 1/2" 10K CIBP , set @ 5522' , KOP of horizontal section @ 5575' , Circ hole w/ mud & spot 5 sks cement on CIBP . Cut & pull 4 1/2" csg from 2695' (65 jts total) . Run tbg @ 1784' , mix & spot 125 sks Class "C" cement @ 14.8 ppg w/ 1.32 yield , up to 1405' , Pull tubing up to 692' , mix & spot 80 sks Class "C" cement up to 450' , POH w/ tbg & top out 64' - 4' w/ 20 sks cement .

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
Address 1: P. O. Box 1706 Address 2: _____
City: Duncan State: OK Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: EOG Resources, Inc.

State of Oklahoma County, Oklahoma , ss.
Candy Driscoll Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Candy Driscoll