

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30717
Name: Downing-Nelson Oil Co. Inc.
Address 1: P.O. Box 372
Address 2: _____
City: Hays State: Ks. Zip: 67601 + _____
Contact Person: Terry W. Piesker
Phone: (785) 735-4363
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Sand Depth to Top: 4166" Bottom: 4173' T.D. 4302
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 195-22.327-00-00
Spot Description: 30'W
SE, SW, NW Sec. 26 Twp. 13 S. R. 22 East West
2,310 Feet from North / South Line of Section
930 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Trego
Lease Name: Loflin Well #: 1-26
Date Well Completed: 9-27-06
The plugging proposal was approved on: 7-28-10 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 8-6-10
Plugging Completed: 8-6-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Sand	Oil and water	Surface	8 5/8"	223'	none
		Long String	5 1/2"	4325'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 75 sxs. 60/40 Poz, 4% Gel with 200# Hulls and followed with 10 sxs. Gel and 255 sxs. of 60/40 Poz, 4% Gel with 200# Hulls. Pressured to 1300# SIP- 900# and held solid. Tied to backside and mixed 5 sxs. 60/40 Poz and pressured to 200#. Job Complete.

Plugging Contractor License #: _____ Name: Quality Oilwell Cementing, Inc.
Address 1: P.O. Box 32 Address 2: _____
City: Russell State: Kansas Zip: 67665 + .0032
Phone: (785) 483-2025
Name of Party Responsible for Plugging Fees: Downing-Nelson Oil Co. Inc.
State of Kansas County, Ellis, ss.
Terry W. Piesker Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 10 2010

KCC WICHITA