

RECEIVED

AUG 04 2010

Form CP-4
March 2009

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Type or Print on this Form
Form must be Signed
All blanks must be Filled

15-073-01082-00-01

OPERATOR: License #: 5394
Name: R.R. Abderhalden
Address 1: 100 S. Main, Suite 510
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: R.R. Abderhalden
Phone: (316) 262-3411
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: EO-3423 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 2064 Bottom: 2143 T.D. 2143
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. ~~15-073-01082-00-01~~ Completed: 9-19-26
Spot Description: _____
NW NE NE Sec. 12 Twp. 22 S. R. 10 East West
4810 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Greenwood
Lease Name: Demalorie Sowder Well #: W-12
Date Well Completed: 9-19-26
The plugging proposal was approved on: 6-22-10 (Date)
by: Mike Heffern (KCC District Agent's Name)
Plugging Commenced: 6-22-10
Plugging Completed: 6-23-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Bartlesville	Oil	Production Surface AND KCC	6 5/8	2070	Cemented to surface

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped sand on bottom. Plugged back depth at 2065. Dumped 5 sax of cement on bottom. Ran tubing to 970 ft. Pumped 15 sax of cement. Pulled tubing to 150 ft. Cemented to surface. Used 20 sax.

Plugging Contractor License #: 5656 Name: R.R.A., INC.
Address 1: 100 S. Main, Suite 510 Address 2: _____
City: Wichita State: Kansas Zip: 67202 + _____
Phone: (316) 262-3411
Name of Party Responsible for Plugging Fees: R.R. Abderhalden
State of Kansas County, Sedgwick, ss.
R.R. Abderhalden Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: R.R. Abderhalden

P-4459

PHILLIPS PETROLEUM COMPANY

610 Petroleum Bldg.
Wichita, Kansas
May 6, 1952

W-12

Re: DeMalorie-Sowder Unit,
Well # 29
NW NE NE, Sec. 11-22S-10 E.
Greenwood County, Kansas
Elevation 1235

RECEIVED
AUG 04 2010

Mr. W. L. Kitsman
Eureka Office
KCC WICHITA

Dear Sir:

We are in receipt of the Lane-Wells Radioactivity and Neutron log surveyed at the above well April 29, 1952. We are listing below the formation markers recorded in this survey:

Tarkio	113 (/ 1122)
Emporia	190 (/ 1045)
Howard	388 (/ 847)
Topeka	483 (/ 752)
Heebner	836 (/ 399)
Toronto	852 (/ 383)
Douglas	870 (/ 365)
Tonganoxie Sand	1020-1037 (/ 215 / 198)
	and 1068-1085 (/ 167 / 150)
Lansing-Kansas City	1153 (/ 82)
Drum	1405 (-170)
Base Kansas City	1571 (-336)
Marmaton	1670 (-435)
Cherokee	1847 (-612)
Bartlesville	2089 (-854)
Sand	o 2089-2097 (-854 -862)
Shaley Sand	2097-2105 (-862 -870)
Sand	2105-2110 (-870 -875)
Shaley Sand	2110-2115 (-875 -880)
Sand	2115-2121 (-880 -886)
Shaley Sand	2121-2128 (-886 -893)
Sand	2128-2141 (-893 -906)
Shale	2141-2143 (-906 -908)
Recorded Total Depth	2143 (-908)
Total Depth	2145 (-910)

Very truly yours,

Roy P. Lehman

RPL/mb
CC: F.W.Shelton
C.W.Cargile
J.S.Williams
L.E.Fitzjarrald
C.A.Daniels
F.J.Latinis

RW
K

RECEIVED
MAY 7 1952
PHILLIPS PETROLEUM CO.
EUREKA OFFICE