

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30705
Name: Younger Energy Company
Address 1: 453 S. Webb Road, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67207 + 1310
Contact Person: Diane Rebstock
Phone: (316) 681-2542
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No C-10 If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 3882 Bottom: 3890 T.D. 3892
Tarkio Depth to Top: 2812 Bottom: 2816 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 145-20,677-0000
Spot Description: _____
- SW SE SE Sec. 27 Twp. 21 S. R. 15 East West
330 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pawnee
Lease Name: Cossman Well #: 1
Date Well Completed: 7/29/1980
The plugging proposal was approved on: 7-6-2010 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 7/06/2010
Plugging Completed: 7/07/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	926'	none
		Production	4-1/2"	3884'	38 jts., 1524'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well had been previously plugged back to 2844'. Set CIBP @ 2800', shot off Production casing @ 1524'. Ran 2-3/8" tubing to 961', pumped 15 sxs of gel and 50 sxs of 60/40 pozmix, 4% gel. Pulled tubing to 437', pumped 40 sxs of 60/40 pozmix, 4% gel. Pulled tubing to 60', pumped 30 sxs of 60/40 pozmix, 4% gel to surface. Used total of 120 sxs.

RECEIVED
AUG 18 2010

Plugging Contractor License #: 7023 Name: Klima Well Service Inc.
Address 1: P.O. Box 48 Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Phone: (620) 793-8888
Name of Party Responsible for Plugging Fees: Younger Energy Company, 453 S. Webb Rd., Suite 100, Wichita, KS 67207
State of Kansas County, Sedgwick, ss.
Diane Rebstock Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Diane Rebstock

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

