

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32924  
Name: Gilbert-Stewart Operating, LLC  
Address 1: 1801 Broadway, Suite 450  
Address 2: \_\_\_\_\_  
City: Denver State: CO Zip: 80202 + \_\_\_\_\_  
Contact Person: Kent Gilbert  
Phone: ( 303 ) 534-1686  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 159-22620-00-00  
Spot Description: \_\_\_\_\_  
SE - NE - NW - \_\_\_\_\_ Sec. 16 Twp. 19 S. R. 9  East  West  
860 Feet from  North /  South Line of Section  
2,400 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Rice  
Lease Name: Lincoln Well #: 9  
Date Well Completed: D & A  
The plugging proposal was approved on: 07-30-10 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Plugging Commenced: 08-07-10  
Plugging Completed: 08-08-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8" new 23#	302'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug well with 180 sacks of 60/40 Poz, 4% gel, 1/4# floseal per sack.  
1st plug @ 3250' with 35 sacks. 2nd plug @ 1200' with 35 sacks. 3rd plug @ 800' with 35 sacks.  
4th plug @ 352' with 35 sacks. 5th plug @ 60' with 25 sacks to surface. Plug rat hole with 15 sacks.  
Job complete @ 1:00 a.m. on 08-08-10 by Quality (tk #4179)

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc.  
Address 1: PO Box 276 Address 2: 8 North Main  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: ( 620 ) 564-3800  
Name of Party Responsible for Plugging Fees: Gilbert-Stewart Operating, LLC

State of Kansas County, Barton, ss.  
Renee Kasselma, Office Manager of Southwind Drilling, Inc.  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Renee Kasselma 08-11-10

RECEIVED

AUG 12 2010

KCC WICHITA

**SOUTHWIND DRILLING, INC.  
PLUGGING ORDERS AND REPORTS**

Lease: Lincoln #9

Plugging received from KCC representative:

Name: Virgil Clothier Date 7-30-10 Time 8:45

1<sup>st</sup> plug @ 3250 ft. 35 sx. Stands: 51

2nd plug @ 1200 ft. 35 sx. Stands: 19

3rd plug @ 800 ft. 35 sx. Stands: 13

4th plug @ 352 ft. 35 sx. Stands: 5 1/2

5th plug @ 60 ft. 25 sx. Stands: 1

Mousehole \_\_\_\_\_ sx.

Rahole 15 sx.

Total Cement used: 180 sx.

Type of cement 60/40 P02, 4% Gel, 1/4" Floseal

Plug down @ 1:00 A.M 8-8-10

Call KCC When Completed:

Name: Duane KUGER Date 8-10-10 Time 8:45

RECEIVED  
AUG 12 2010  
KCC WICHITA

# QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 4179

Date	Sec.	Twp.	Range	County	State	On Location	Finish
8-7-10	16	19	9	Rice	Kansas		1:00 AM
Lease Lincoln	Well No. 9		Location Chase 4W 13E S104				
Contractor Southern Drilling Rig 3				Owner To Quality Oilwell Cementing, Inc.			
Type Job Plug				You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size		T.D. 3323		Charge To Gilbert A Stewart			
Csg.		Depth		Street			
Tbg. Size		Depth		City State			
Tool		Depth		City State			
Cement Left in Csg.		Shoe Joint		The above was done to satisfaction and supervision of owner-agent or contractor.			
Meas Line		Displace		Cement Amount Ordered 180 cubic 42 bag			

**EQUIPMENT**

Pumptrk 5	No.	Cement Helper	5
Bulktrk 10	No.	Driver	10
Bulktrk	No.	Driver	10

Common
Poz. Mix
Gel.
Calcium
Hulls
Salt
Flowseal
Kol-Seal
Mud CLR 48
CFL-117 or CD110 CAF 38
Sand
Handling
Mileage

**JOB SERVICES & REMARKS**

Remarks:
Rat Hole:
Mouse Hole:
Centralizers:
Baskets:
D/V or Port Collar:
1st Plug @ 3270 258
2nd " " 1200 323
3rd " " 800 35
4th " " 300 323
5th " " 100 355
Rat Hole 154

Float Equipment
Guide Shoe
Centralizer
Baskets
AFU Inserts
Float Shoe
Latch Down
1 55 Wood Plug
Pumptrk Charge
Mileage

**Signature:** *[Handwritten Signature]*

**RECEIVED**  
AUG 12 2010  
Total Charge  
**KCC WICHITA**