

AUG 02 2010

Form CP-4
March 2009

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6131
Name: Drillers & Producers, Inc
Address 1: P.O. Box 385
Address 2: _____
City: Newton State: Ks Zip: 67114 + _____
Contact Person: Bill Hanson
Phone: (316) 841-0022
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 2346' Bottom: 2372' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 115-21072 0000
Spot Description: _____
S2 SE SW Sec. 5 Twp. 22 S. R. 4 East West
370 Feet from North / South Line of Section
3,472 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Marion
Lease Name: Lathrop-Hawk A Well #: 2
Date Well Completed: 2-12-84
The plugging proposal was approved on: 6-30-10 (Date)
by: Verbal per phone (KCC District Agent's Name)
Plugging Commenced: 6-30-10
Plugging Completed: 6-30-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	212'kb	
		casing	4 1/2'	2546'kb	350'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

set 2 7/8" tubing at 2350' pumped 70 sks class A 3%cc and displaced to 2350', pulled tubing, ran wire line and tagged cement at 1510', shot off 4 1/2" casing at 350' pulled out, ran 2 7/8" tubing down to 262', pumped 152 sks class A to surface, cement circulated in the cellar

Plugging Contractor License #: 5870 Name: Phillips Well Service
Address 1: P.O. Box 1263 Address 2: _____
City: El Dorado State: Ks Zip: 67042 + _____
Phone: (316) 321-6650
Name of Party Responsible for Plugging Fees: Drillers & Producers Inc.

State of Ks County, Harvey, ss.
Drillers & Producers Inc. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Willie Hanson