

RECEIVED

AUG 02 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 6568 Name: Kaiser-Francis Oil Company Address 1: P. O. Box 21468 Address 2: City: Tulsa State: OK Zip: 74121 + 1468 Contact Person: Charlotte Van Valkenburg Phone: (918) 491-4314 Type of Well: (Check one) [X] Oil Well [] Gas Well [] OG [] D&A [] Cathodic [] Water Supply Well [] Other: [] SWD Permit #: [] ENHR Permit #: [] Gas Storage Permit #: Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No Producing Formation(s): List All (If needed attach another sheet) Lansing Depth to Top: 4406 Bottom: 4414 T.D. Morrow Depth to Top: 5624 Bottom: 5628 T.D. St. Louis Depth to Top: 5952 Bottom: 5956 T.D. 5973

API No. 15 - 175-20168 0000 Spot Description: C-SE NW Sec. 7 Twp. 33 S. R. 31 [] East [X] West 1980 Feet from [X] North / [] South Line of Section 1980 Feet from [] East / [X] West Line of Section Footages Calculated from Nearest Outside Section Corner: [] NE [X] NW [] SE [] SW County: Seward Lease Name: Graber Well #: 1 Date Well Completed: 2/24/72 The plugging proposal was approved on: 6/25/10 (Date) by: Steve Durrant (KCC District Agent's Name) Plugging Commenced: 7/13/10 Plugging Completed: 7/15/10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Pulled Out). Rows include Lansing, Morrow, and St. Louis formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Circ'd hole with mud. Set 50 sx cmt plug from 1590'-1440'. Set 40 sx cmt plug from 630'-510'. POOH w/5 1/2" casing & LD. Loaded hole with mud to 40'. Set 10 sx cmt plug from 40'-surf. Cut off & capped 8 5/8" csg 3' below GL.

Plugging Contractor License #: 6568 Name: Kaiser-Francis Oil Company Address 1: P. O. Box 21468 Address 2: City: Tulsa State: OK Zip: 74121 + 1468 Phone: (918) 491-4314

Name of Party Responsible for Plugging Fees: Kaiser-Francis Oil Company State of Oklahoma County, Tulsa, ss. Charlotte Van Valkenburg [X] Employee of Operator or [] Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]