

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32679  
Name: AAS Oil Company Inc.  
Address 1: 2508 Edgemont Drive  
Address 2: Suite # 4  
City: Arkansas City State: Ks Zip: 67005 +       
Contact Person: Gary Anstine  
Phone: ( 620 ) 441-8165  
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic  
☐ Water Supply Well ☐ Other:      ☐ SWD Permit #:       
☐ ENHR Permit #:      ☐ Gas Storage Permit #:       
Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 3102 Bottom: 3165 T.D. 3165  
     Depth to Top:      Bottom:      T.D.       
     Depth to Top:      Bottom:      T.D.     

API No. 15 - 035-21016 - 00-90  
Spot Description:       
N2 - NW - NE Sec. 16 Twp. 33 S. R. 6 ☒ East ☐ West  
326 Feet from ☒ North / ☐ South Line of Section  
2,175 Feet from ☒ East / ☐ West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
☒ NE ☐ NW ☐ SE ☐ SW  
County: Cowley  
Lease Name: Fry "A" Well #: 5  
Date Well Completed: 1976  
The plugging proposal was approved on:      (Date)  
by:      (KCC District Agent's Name)  
Plugging Commenced: 5-24-10  
Plugging Completed: 5-24-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	oil&water	Surface	8.625"	165'	0
		Production	4.5"	3164'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 4.5" casing @ 349'. Ran 2" tubing to 3049' spotted 50 sacks 4% CACL. Pulled tubing to 2030' spotted 50 sacks 4% CACL. Pulled tubing to 349' mixed 163 sacks Class A circulated cement to surface inside 4 1/2" and on the annulus. Pulled tubing and topped 4 1/2" off with cement.

Plugging Contractor License #: 31539 Name: SAM'S Well Service  
Address 1: PO Box 2444 Address 2:       
City: Ponca City State: OK Zip: 74602 + 2444  
Phone: ( 620 ) 441-3943  
Name of Party Responsible for Plugging Fees: AAS Oil Company  
State of Cowley County, Kansas, ss.  
Gary Anstine ☐ Employee of Operator or ☒ Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature:     

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
AUG 12 2010  
KCC WICHITA