

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County, Sec. 14 Twp. 13 Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Franco Central Oil Co. & Mallonee Drilling Company, Inc.

Lease Name Speere Well No. 1

Office Address 820 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-1 19 57

Application for plugging filed 9-1 19 57

Application for plugging approved 9-1 19 57


Plugging commenced 9-1 19 57

Plugging completed 9-1 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3283 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200	8-5/8	200	None - cement circulated.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 200', 1 sack hulls, 20 sacks cement.
Plug set at 40', 10 sacks cement to top of hole.

09-13-1957

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.

Address 820 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. E. Mallonee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee

820 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 57

My commission expires 12-14-57

Notary Public. [Signature]

PLUGGING
FILE SEC 14 T 13 R 14W
BOOK PAGE 42 LINE 9

15-167-00310-00-00

DRILLERS' LOG

#1 Speere
SE SE SE Section 14-13-14W
Russell County, Kansas

OWNER: Franco Central Oil & Mallonee
CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: August 20, 1957
COMPLETED: September 1, 1957
D & A

FROM	TO	DESCRIPTION
0	40	Post rock shale
40	110	Sand and shale
110	200	Sand, rock and shale
200	310	Shale and iron
310	381	Sand and iron
381	824	Red bed and shale
824	865	Anhydrite
865	1500	Shale and shells
1500	1510	Lime and shale
1510	1765	Lime
1765	1780	Lime and shale
1780	2125	Lime
2125	2205	Shale
2205	2473	Shale and shells
2473	2510	Lime
2510	2520	Shale and sand
2520	2605	Shale and shells
2605	2685	Lime and shale
2685	3283	Lime
3283		Rotary Total Depth

CASING RECORD

5 joints (201') 8-5/8" casing set at 200'
with 110 sacks Pozmix, 2 sacks CC.
Cement circulated.

TOPS

Elevation		1813 K.B.
Anhydrite	824	✓ 989
Heebner	2911	-1098
Toronto	2928	-1115
Lansing K.C.	2966	-1153
Base K.C.	3177	-1364
Arbuckle	3262	-1449
R.T.D	3283	-1470

Drill Stem Test 3135 - 3153
Open 1 hour, recovered 90' salt water.
IBHP 1022' in 20", 914' FBHP in 20"

I hereby certify that to the best of my knowledge and belief, the above represents a true and accurate Drillers' Log of the captioned well.

R. E. Mallonee
R. E. Mallonee

STATE OF KANSAS
COMMISSIONER OF GEOL. & MINES
09-13-1957
SEP 13 1957
CONSERVATION DIVISION
Wichita

State of Kansas) ss
County of Sedgwick)

Subscribed and sworn to before me this 5th day of September, 1957.

My commission expires 12-14-57

PLUGGING
FILE SEC 14 T 13 R 14W
BOOK PAGE 42 LINE 9

Martha Gorges
Notary Public (Martha Gorges)