

State of Kansas



15-051-30252-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

4-18-1966
APR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of HELLAR DRILLING CO. has this
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: HELLAR DRILLING CO & HELAR DRILLING CO

Complete Address: 337 Union Center Wichita, Kans.

Lease Name: Madden Well No. 1

Location: SE-NW-NE Sec. 5 Twp. 11 Rge. 17 (E)(W) X

County Ellis Total Depth 3701 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

~~Set pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 25 sac cement thru drill pipe, heavy mud to 200 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hails and 10 sac cement, cementing
to base of collar. Plug rat hole with two sac cement.~~

Very truly yours,

Geo Massey
Conservation Division Agent