



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rutt of Shields Oil Producers has this date requested permission to plug the following described well:

Mr. Rutt guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Russell, Ks.

Lease Name: Amoco - Carmichael Well No. 1

Location: NW NE SE Sec. 5 Twp. 11 Rge. (E)(W) 17

County: Ellis Total Depth 3170' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rutt was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 550' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
Conservation Division Agent