



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
5-20-1966  
MAY 20 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Wienrich of D-D Drilling has this date requested permission to plug the following described well:

Mr. Wienrich guarantees payment of the plugging fee.

Operator's full Name: D-D Drilling Co. Inc.

Complete Address: 707 ~~South~~ Schweiter Ag. Wichita, Kans

Lease Name: Rumble Well No. 1

Location: N/2 S/2 NW Sec. 5 Twp. 11 Rge. 17 (E)(W) X

County Ellis Total Depth 3150 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Wienrich was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 600 ft.,  
and displace 25 sax cement thru drill pipe, heavy mud to 230 ft., set  
cementing plug and displace 20 sax cement thru drill pipe, heavy mud  
to 40 ft., set cementing plug, 1/2 sac hulls and 8 sax cement, cementing  
to base of cellar. Plug rat hole with two sax cement.

Very truly yours,

Geo Massey  
Conservation Division Agent