



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. B. F. Brown of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. O. A. Sutton guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name: Hill Well No. # 1

Location: NW SE SW Sec. 13 Twp. 13 Rge. 14 (E)(W) W

County: Russell Total Depth 3320 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. B. F. Brown was instructed to plug the well as follows:

8 5/8" 228' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 40 sax cement thru drill pipe. Mud to 220', set plug, & displaced 25 sax cement thru drill pipe. Mud to 40', plug, & displaced 10 sax cement with Halliburton Cementing Company's pump truck, cementing to base of cellar?

RECEIVED
 STATE CORPORATION COMMISSION

Very truly yours,

DEC 27 1967

12-27-1967
 CONSERVATION DIVISION
 Wichita, Kansas

Don Truman
 Conservation Division Agent