



15-167-20215-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 26 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 07-26-1968

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company has this date requested permission to plug the following described well:

Mr. Clarence Wilhelm guarantees payment of the plugging fee.

Operator's full Name: Clarence Wilhelm

Complete Address: 316 Grant Street, Russell, Kansas 67665

Lease Name: Evans Well No. # 1

Location: SE NW NW Sec. 20 Twp. 13 Rge. 14 (E)(W) W

County: Russell Total Depth 3298 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" 200' Cwc.

Circulated hole with heavy mud to 420', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 190' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Halliburton Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don Luman  
 Conservation Division Agent