

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

OPERATOR: License #: 5970
Name: John A Elmore
Address 1: 776 Hwy 99
Address 2: PO Box 87
City: Sedan State: Ks Zip: 67361+
Contact Person: John A Elmore
Phone: (620) 249-2519
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Peru Depth to Top: 1140 Bottom: 1160 T.D. 1195

API No. 15 - 019-24335-0002
Spot Description: NW 1/4
NW NW SW NE Sec. 34 Twp. 33 S. R. 11 East West
3925 Feet from North South Line of Section
5115 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chautauqua
Lease Name: CW Floyd Well #: 6
Date Well Completed: 10-11-83
The plugging proposal was approved on: 6-24 (Date)
by: Dwaine Sims (KCC District Agent's Name)
Plugging Commenced: 6-24-10
Plugging Completed: 6-25-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Peru	Water	Production	4 1/2	1182'	None
		Surface	7"	40'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

300' of 2" IN Bottom of well Tried to Fish Out Pulled Tubin Above Fish Into Got Fishing Tool To Release At 300' From Bottom Ran 1" To 860' Gel Hole Spotted 100' Cement Plug Pulled 1" upto 600' spotted 50' Cement Plug Pulled upto 350' Cemented To surface with 35 sks.

Plugging Contractor License #: 32884 Name: Elmores Inc
Address 1: 776 Hwy 99 Address 2: Box 87
City: Sedan State: Ks Zip: 67361+
Phone: (620) 249 2519
Name of Party Responsible for Plugging Fees: John Elmore
State of Kansas County, Chautauqua, ss.
John A Elmore Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: John A Elmore

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 02 2010
KCC WICHITA