


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ellis County, Sec. 7 Twp. 11S Rge. 17 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

E/2 SE SE  
Lease Owner Energy Reserves Group, Inc.  
Lease Name Bemis Shutts SWD Well No. 4  
Office Address 925 Patton Rd, Great Bend, KS 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Salt Water Disposal Well  
Date Well completed October 3 1941  
Application for plugging filed September 19 1984  
Application for plugging approved September 28 1984  
Plugging commenced October 19 1984  
Plugging completed October 30 1984

Reason for abandonment of well or producing formation  
Not taking adequate disposal water.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	38	None
				10-3/4"	1105	None
				7"	3365	None
				5-1/2"	3424	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10-19-84 Pumped 600 sxs lite cement down 5-1/2" csg. Max Press 500 psi.

10-30-84 Ran measuring line and found cement top at 1620'.  
Took injection rate of 1.5 BPM @ 200 psi. Pumped 160 sxs  
lite cement down casing. Max Pressure 600 psi. SIP 300 psi.  
Plugging completed at 9:15 A.M. 10-30-84.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Barton, ss.  
Jim W. Sullivan (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim W. Sullivan  
925 Patton Rd, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1984

My commission expires My Appt. Exp. Sept. 9, 1987



RECEIVED  
SINGLE COPY PUBLIC COMMISSION  
RW0  
NOV 26 1984  
11-20-84  
CONSERVATION DIVISION  
Wichita, Kansas