


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec 7 Twp. 11S Rgs. 17W (W)
Location as "NE/CNW/SW" or footage from lines C W/2 SE NE
Lease Owner Clinton Oil Company
Lease Name Nona Henderson 'A' Well No. #5
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 4 1941
Application for plugging filed May 21 1973
Application for plugging approved May 22 1973
Plugging commenced 6/4/73 19
Plugging completed 6/6/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production November 10 1972
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Arbuckle O. H. Depth to top 3411' Bottom 3414' Total Depth of Well 3414 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	1130	none
				7"	3411	2050'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3381', dumped 7 sacks cement.
Shot pipe at 2272', 2180', 2090', pulled 68 joints. Set
15' rock bridge at 400' and dumped 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1973

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

THE DICKEY OIL COMPANY
Henderson-A No. 5

COMMENCED: 4-9-41
COMPLETED: 5-4-41

LOCATION: C-W₂ SE₁ NE₁ 7-11-17
Ellis County, Kansas
ELEVATION: 1859

Casing Record

60' 15 1/2"
1130' 10"
3413' 2" 7"

surface	10
sand	55
clay	61
shells and shale	545
sandy shale	595
shale	635
sand	765
red rock	1105
anhydrite - top 1105	1130
lime	1140
red bed	1375
red bed, salt	1550
shale and shells	1700
broken lime	1820
shale and shells	1940
broken lime	2015
shale and shells	2095
lime	2145
broken lime	2200
shale and shells	2350
broken lime	2400
shale	2640
broken lime	2858
Top Topeka	2858
Top Lansing	3070
lime	3330
red rock	3347
chert	3380
cherty conglomerate	3387
Simpson Dolomite	3396
green shale	3410
sand	3411 1/2
Top of Arbuckle	3411 1/2
Arbuckle lime	3414

(Top of Arbuckle corrected to 3410)

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1973
CONSERVATION DIVISION
Wichita, Kansas