

15-051-01355

LEASE NAME Henderson A

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 6

2970' Ft. from S Section Line

2260' Ft. from E Section Line

SEC. 7 TWP. 11 RGE. 17 (E) of (N)

COUNTY Ellis

LEASE OPERATOR White Eagle Resources Corp.

ADDRESS 881 West Chestnut Circle Louisville, CO 80027

PHONE# (303) 665-1496 OPERATORS LICENSE NO. 31430

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 3/57

Plugging Commenced 1/20/98

Plugging Completed 1/20/98

The plugging proposal was approved on 1/20/98 (date)

by Hubert Deines (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Log was enclosed with CP-1

Producing Formation Arbuckle Depth to Top 3423 Bottom 3425 T.D. 3525

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	Surface	218	8 5/8"	218'	None
		Surface	3526	5 1/2"	3526'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each s
Allied Cementing pumped down 5 1/2" 40 sks. cement, followed by 14 sk. gel spacer, followed
by 160 sks. of cement. Max. pressure was 500#'s SIP was 400#'s. All cement was 60/40 poz.
with 10% gel. 8 5/8" x 5 1/2" annulus had cement to surface. Plug down @ 11:30 AM 1/20/98
State man on location was Rich Williams.

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31 Russell KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources Corp.

STATE OF Kansas COUNTY OF Rooks, ss.

Robert Plante

Agent
(~~Employee~~ of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Robert E. Plante

(Address) Box 86 P.O. Box 211e 1998 67663

RCWD
02-02-98

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1998

Irene Fellhoelter
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM

