

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-05101675-00-01  
API NUMBER 15-051-01675-0001

LEASE NAME Collins-Henderson

WELL NUMBER #6SWD  
3630 NGC KCC  
4950 Ft. from S Section Line  
4620 Ft. from E Section Line

SEC. 7 TWP. 11SRGE. 17 #1 or (W)

COUNTY Ellis

Date Well Completed 4-10-78

Plugging Commenced 3-5-87

Plugging Completed 3-5-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558, Garden City, Ks. 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well TA'd disposal

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas Dist #6

Is ACO-1 filed? yes If not, is well log attached? Previously filed

Disposal  
Formation Cedar Hills Depth to Top 750 Bottom 820 T.D. 3393  
PBDT 1123

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cedar Hills	Water	0	115	16"	115	0
		0	1123	10-3/4	1128	0
		0	232	5 1/2	232	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set.

Hook up Halliburton to 5 1/2" Csg. Mix and pump 125 sks 65/35 Poz, 10% gel 2% econolite w/ 1 sk hulls in first portion of cement. Max psi - 500#. TSTP - 400#. Filled csg. to surface with cement. Mixed at 10.8#/gal with 3.63 ft 3/sk.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.           

Address Hays, Kansas


STATE OF Kansas COUNTY OF Finney, ss.

Millard L. Lindsay (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Millard L. Lindsay

(Address) P.O. Box 558, Garden City, KS

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1987



Betty J. Lindsey  
STATE CORPORATION COMMISSION  
NOTARY PUBLIC

My Commission Expires: August 6, 1990

RECEIVED  
MAR 9 1987  
03-08-87  
CONSERVATION DIVISION  
Wichita, Kansas