

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-05688-00-00

LEASE NAME R. Stein

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line
2310 AUB KCC
Ft. from E Section Line

LEASE OPERATOR Quinoco Petroleum, Inc.

NWNWSE SEC. 7 TWP. 11S RGE. 17 (E) or (W)

ADDRESS P O Box 378111 Denver, CO 80237

COUNTY Ellis

PHONE# (303) 850-7373 OPERATORS LICENSE NO. 03613

Date Well Completed 1938

Character of Well Oil

Plugging Commenced 12-5-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-5-89

The plugging proposal was approved on 10/23/89 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3437 Bottom 3440 T.D. 3440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf	To	Size	Put In	Pulled out
Arbuckle	oil	Surf	69	5 1/2"	69	
		Surf	1161	10"	1161	
		Surf	3447	7"	3447	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran 2 3/8" tbg to 2628'. Pumped 150 sx 60/40 poz w/8% gel mixed with 500# hulls. Pulled tbg to 1620', filled csg w/cmt. Pulled tbg. Filled csg w/cmt, total of 350 sx w/500# hulls. Hooked on to 10 3/4" csg, pumped 50 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P O Box 579 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF _____ COUNTY OF _____, ss.

Suzanne E. Meadows, Sr. Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Suzanne E. Meadows

(Address) P O Box 378111 Denver 80231

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 90

RECD
STATE OF KANSAS
APR 18 1990

CONSERVATION DIVISION
Wichita, Kansas

Robert Cardinal
Notary Public

My Commission Expires: May 21, 1990

E. Log File 7-11-71



Gamma Ray

15-051-05688-00-00

FILE NO.	COMPANY	CLINTON OIL COMPANY		
	WELL	R. STEIN NO. 1		
	FIELD	BEMIS-SHUTTS		
	COUNTY	ELLIS	STATE	KANSAS
LOCATION:				Other Service
NW - NW - SE				
SEC	7	TWP	11S	RGE 17W

Permanent Datum	CEMENT FLOOR	Elev.	-	Elevations:
Log Measured from	CEMENT FLOOR	0	Ft. Above Permanent Datum	KB N/A
Drilling Measured from	- - -			DF 1904
				GL N/A

Date	7-16-71
Run No.	ONE (DW)
Type Log	G/R
Depth-Driller	3450*
Depth-Logger	3439.5
Bottom Logged Interval	3438.5
Top Logged Interval	2700
Type Fluid in Hole	OIL & WATER
Salinity Ppm Cl.	-
Density Lb./Gal.	-
Level	APPROX 1050
Max. Rec. Temp. Deg. F	-
Opr. Rig Time	1-1/2 HRS.
Recorded By	KIRCHNER
Witnessed By	MR. HUTTON

Run No.	Bore Hole Record				Casing Record			
	Bit	From	To	Size	Wgt.	From	To	
1	-	-	-	15-1/2	-	0	69	
2	-	-	-	10-3/4	32.75	0	1061	
3	-	-	-	7	24	0	3447	
				OPEN HOLE		3447	3450	
* PROBABLY MEASURED FROM OLD D.F.								
BOTTOM OF 7" CASING SHOE LOCATED BY D.A. AT 3436.5								