

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Brungardt Oil & Leasing, Inc.

Address: PO Box 871, Russell, KS 67665

Phone: (785) 483-4975 Operator License #: 3956

Type of Well: D & A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-10-2010 (Date)

by: Rich Williams (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-141-20,411 0000

Lease Name: Hirst "A"

Well Number: 1

Spot Location (QQQQ): SE - NW - NW - SW  
2,090 Feet from  North /  South Section Line

430 Feet from  East /  West Section Line

Sec. 9 Twp. 10 S. R. 12  East  West

County: Osborne

Date Well Completed: 8-9-10

Plugging Commenced: 8-10-10

Plugging Completed: 8-10-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 3,985', pump 25 sax cement thru drill pipe; run drill pipe to 970', pump 25 sax cement thru drill pipe; run drill pipe to 690', pump 100 sax cement thru drill pipe; run drill pipe to 250', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184

Address: PO Box 709, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Brungardt Oil & Leasing, Inc.

State of KANSAS County, RUSSELL, ss.

Burton Beery Contractor  
(Employee of Operator or Operator)

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Burton Beery

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 17<sup>th</sup> day of August, 2010

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
SEP 13 2010  
KCC WICHITA




# Shields

Russell, Kansas

## WELL LOG

Operator: Brungardt Oil & Leasing, Inc.  
 Well: Hirst "A" #1  
 Commenced: 7-30-2010  
 Completed: 8-10-2010  
 Contractor: Shields Drilling Co.

Well Description: 2,090' FSL, 430' FWL  
 SW/4 Sec. 9-10S-12W  
 Osborne Co., KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/150 sax

Elevation: 1,847 KB

Treatment: D & A

Production:

Tops:

..... Figures Indicate Bottom of Formations .....

Sand & shale	350'
Sand	690'
Sand & redbed	953'
Anhydrite	986'
Shale	2,700'
Shale & lime	3,080'
Lime	3,333'
Conglomerate	3,523'
Mississippi	3,583'
Viola	3,678'
Simpson	3,945'
Arbuckle	4,006'
Total Depth	4,050' RTD

RECEIVED  
 SEP 13 2010  
 KCC WICHITA

Notes