

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3830
Name: AX&P, Inc
Address 1: 20147 200 Road
Address 2: _____
City: Neodesha, State: KS Zip: 66757 + _____
Contact Person: J J Hanke
Phone: (620) 325-5212
Type of Well: (Check one) ☐ Oil Well ☒ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Old shallow gas zone Depth to Top: 300' Bottom: 305' T.D. 305'205
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 205-19862-00-00
Spot Description: se se ne nw
_____-_____-_____- Sec. 29 Twp. 30 S. R. 16 ☒ East ☐ West
4,236 Feet from ☐ North / ☒ South Line of Section
2,756 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☐ SE ☐ SW
County: Wilson
Lease Name: Unit 1 Well #: WW - OW#2
Date Well Completed: 1905
The plugging proposal was approved on: 9/1/10 (Date)
by: Alan Dunning (KCC District Agent's Name)
Plugging Commenced: 9-1-10
Plugging Completed: 9-2-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
gas zone	gas	surface	8"	150' est	zero

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Surface casing was bent over at 8' underground. Dug up old casing; cut off old casing; slipped 10" pipe over it; cemented to surface and refilled hole. Started drilling with rotary; drilled up old wood plug and other debris. drilled to 305' when hard material was hit, probably TD. Received permission to plug and called in cementing contractor. Cemented to surface with 147 sx Portland cement. P/O pipe and filled hole from top to surface.

Plugging Contractor License #: 3830 Name: AX&P, Inc.
Address 1: 20147 200 Road Address 2: _____
City: Neodesha State: KS Zip: 66757 + _____
Phone: (620) 325-5212
Name of Party Responsible for Plugging Fees: AX&P, Inc.
State of Kansas County, Wilson, ss.
Jurgen J. Hanke ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Kepley Well Service, LLC

19245 Ford Road
Chanute, KS 66720

Invoice

Date	Invoice #
9/2/2010	A-45226

Bill To

AX&P, Inc.
20147 200 Road
Neodesha, KS 66757

Wolf West #OW02
Wilson County

Terms	Due Date
Net 30 days	10/2/2010

Description	Qty	Rate	Amount
Pump Truck Plug well with cement	1	400.00	400.00T
Vacuum Truck Haul water	2.5	70.00	175.00T
Cement Sales Tax	147	8.00 6.30%	1,176.00T 110.31
Total			\$1,861.31
Payments/Credits			\$0.00
Balance Due			\$1,861.31

RECEIVED

SEP 13 2010

KCC WICHITA