


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 8 Twp. 11 Rge. 17 (E) (W)
Location as "NE/CNW&SW&" or footage from lines SE-NW/NW/SE AWB KCC
Lease Owner Morgenstern & Spector Pipe & Supply Co.
Lease Name Day Well No. # 2
Office Address Box 661, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1-20-52 19
Application for plugging filed Yes Feb. 17, 1958 19
Application for plugging approved Yes " 18, " 19
Plugging commenced 4-15 1958
Plugging completed 4-18 1958
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production February 1958
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3461 Bottom 3479 Total Depth of Well 3480' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1141	none
				5 1/2"		1,737'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3480'.
Plugging started 4-15-58. Finished 4-18-58.
Plugged off bottom with sand to 3050' and dumped 4 sacks cement.
Shot 5 1/2" casing at 1,737'. Circulated mud. Pumped 20 sacks cement at 500'. Pulled pipe to 200'. Pumped 20 sacks, came on out of hole.
Filled hole with mud to 40'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1958
4-28-58

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 1958

My commission expires November 8, 1960.
Betty S. Edman Notary Public.

PLUGGING
FILE SEC 8 T 11 R 17a
BOOK PAGE 83 LINE 14


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Day No. 2

SEC. 8 T. 11 R. 17W
SE NE SE

Total Depth. 3480 R.B.
Comm. 12-13-51 Comp. 1-20-52
Shot or Treated.
Contractor. Jackson Drlg.
Issued. 3-15-52

County Ellis
KANSAS



Elevation. 1906 D.F.

Production. 25 bbls. temp. prod.

Figures Indicate Bottom of Formations.

sand & shale	145
shale, sand & shells	250
shale & shells	560
pyrite & sand	640
sand	805
shale-	960
red bed & shells	1065
red bed strkd w/sand	
& pyrite	1140
anhyd.	1185
red bed & shells	1225
shale & shells	1625
shale & salt	1750
shale & lime	1875
lime	2280
lime & shale	2379
lime	2400
lime & shale	2965
lime	3011
lime & shale	3037
lime	3091
lime & shale	3185
lime	3262
lime & shale	3274
lime	3392
lime & shale cherty	3422
lime	3427
shale, chert & lime	3462
arb. lime	3480
Total Depth R.B.	

Tops:	
anhyd.	1140
Heebner	3092
Dodge	3111
Mansing	3134
Base C.C.	3378
Congl.	3390
Simpson	3431
Arb.	3461

Schlumberger run
D.S.T. 3171-3218, open 1 hr, rec. 6' mud.
3463-68, open 1 hr, rec 1800' oil, 30'
sulphur wtr. 970, BHP.

Co f. 12 shots 3460064, no results, 12 shots
3464-68, 150' fluid in 1/2 hr, filled up
with wtr. Plastic plug at 3466 1/2, swb. 2 BOPH &
10 gl. wtr. 150 Gl., swb 10 BOPH & 17 B.PH
1200' off bottom. Swb. 100 BO in 10 hr. test.

RECEIVED
FEB 17 1952
DIVISION
Wichita, Kansas

LOGGING
D.S.T. 11 R. 17W
BOOK PAGE 83 LINE 14