


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Ellis County. Sec. 8 Twp. 11 Rge. 17 (E) (W) B
~~NW/NW/SE~~ NW/SE AWB
Lease Owner Morgenstern & Pector Pipe & Supply Co. KCC
Lease Name Day Well No. #4
Office Address Box 661, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 9-18-52 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 4-25 19 58
Plugging completed 4-26 19 58
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production February 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3431 Bottom 3434 Total Depth of Well 3954 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	Casing	None
				5 1/2"		No recovery

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 4-25-58. Finished 4-26-58.
Took tension. Unpacked braden head, took out slips and got ready to squeeze well. Squeezed well with 50 sacks gel mud and 60 sacks cement.
Well completed.

RCWD
05-12-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1958

Petty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 8 T. 11 R. 17
BOOK PAGE 83 LINE 15

15-051-04788-00-00


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Day No. 4

SEC. 8 T. 11 R. 17W
NW SW SE

Total Depth. 3954 R.B.
Comm. 8-27-52 Comp. 9-18-52
Shot or Treated.
Contractor. Westgate Drilling Co.
Issued. 10-25-52

County Ellis
KANSAS



Elevation. 1859 D. J.

Production. SWDW

CASING:

8 5/8" 188 cem. w/175 sx.
5 1/2" 3510 cem. w/1000 sx.

Figures indicate Bottom of Formations.

sand	30
gravel	50
shale & sand	150
shale	235
shale & red bed	600
sand	795
shale & shells	1110
Anhyd.	1145
shale & shells	1575
shale & salt	1700
lime & shale	2080
lime	2155
lime & shale	2610
shale	2800
lime & shale	3070
lime	3100
lime & shale	3165
lime	3347
shale & lime	3358
Cherty Congl.	3385
shale	3395
Congl. & lime	3434
lime & chert	3437
Arbuckle lime	3894
lime w/shale	3908
lime	3954 RB
Total Depth	

Tops:	
Anhydrite	1108-43
Heebner	3046
Lansing	3087
Conglomerate	3382
Arbuckle	3434

No acid or perforations. Began using as salt water disposal well on 9-18-52 under 28 point vacuum. No test taken.

RECEIVED

FEB 17 1953

COURTESY OF DIVISION
Wichita, Kansas

DRILLING
T. 11 R. 17W
BOOK PAGE 83 LINE 16