


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Location as "NE/CNW/SW" or footage from lines Ellis County. Sec. 8 Twp. 11 Rge. 17 (E) W (W)  
Lease Owner Meltzer Oil Company  
Lease Name Gumble Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-15-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9-19-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3423 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	825'	None
				5-1/2"	3417'	872'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3423', sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dumpbailer. Pulled 5 1/2" casing, and squeezed well with 20 sacks of gel mud and 125 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
SEP 29 1966  
CONSERVATION DIVISION  
Wichita, Kansas  
09-29-66

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 66

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

METZER OIL CO.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

112 Union National Bk. Bldg., Wichita, Kansas


15-051-02131-6057

Company - THE PHIL-HAN OIL COMPANY  
Farm - Gumble No. 1

SEC. 8 T. 11 R. 17W  
S1/2 NW

Total Depth. 3423'  
Comm. 5-21-47 Comp. 6-4-47  
Shot or Treated. Acid. w/500 gals.  
Contractor.  
Date 8-23-47

County. Ellis  
KANSAS



CASING:

8-5/8" 825' Cem. w/400 sx  
5-1/2" 3417' Cem. w/ 75 sx

Elevation. \_\_\_\_\_

Production. 143 bbls oil

Figures Indicate Bottom of Formations.

shale & sand	70
shale & shells	320
shale, sand & shells	785
red rock	1110
anhydrite	1150
shale, shells & salt	1460
salt & shale	1670
shale, shells & lime	1745
lime	1875
lime & shale	2015
lime	2265
lime & shale	2290
lime	2365
lime & shale	2815
lime	3380
conglomerate	3400
conglomerate & sand	3418
Arbuckle lime	3423
Total Depth	

*note*

RECEIVED  
STATE COMMISSION

DEC 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

Tops:	
Topeka	2824
Hæbner Shale	3053
Lansing K. C.	3104
Conglomerate	3367
Arbuckle	3416

Drilled plug 3424  
1/2 BOPH, no wr.