


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 8 Twp. 11S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines N/2 NW NE  
Lease Owner Dunne-Gardner Petroleum, Inc.  
Lease Name Gilbert Well No. 1  
Office Address 300 Schweiter Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 18, 19 66  
Application for plugging filed April 21, 19 66  
Application for plugging approved 19  
Plugging commenced April 18, 19 66  
Plugging completed April 18, 19 66  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3481 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	210'	8-5/8"	4-11-66	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 540 feet. Set plug with 1/4 sack hulls, 20 sacks cement. Mud to 200 feet. Set plug with 1/4 sack hulls, 20 sacks cement. Mud to 40 feet. Set plug with 1/4 sack hulls, 10 sacks cement.

RECEIVED  
APR 25 1966  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Dunne-Gardner Petroleum, Inc.  
Address 300 Schweiter Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Don Gardner (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
300 Schweiter Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 66

My commission expires November 9, 1969

[Signature]  
Marilyn E. Fox  
Notary Public.

DRILLER'S LOG

OPERATOR: Dunne-Gardner Petroleum, Inc.  
300 Schweiter Building, Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.

LEASE: GILBERT

WELL: No. 1

LOCATION: N/2 NW NE Section 8-11S-17W,  
Ellis County, Kansas

DATE COMMENCED: April 11, 1966

DATE COMPLETED: April 18, 1966

CASING: 8-5/8" surface pipe @ 210' w/200 sacks

FROM:	<u>TO:</u>	
0	100	Clay and Shale
100	209	Shale
209	477	Shale and Sand
477	571	Shale
571	587	Iron Pyrite and Sand
587	650	Shale and Shells
650	780	Sand
780	1127	Red Bed and Shale
1127	1175	Anhydrite
1175	1979	Shale and Shells
1979	3033	Lime and Shale
3033	3325	Lime
3325	3411	Lime and Chert
3411	3445	Cherty Lime
3445	3481	Lime
3481		Total Depth

RECEIVED  
THE CORPORATION COMMISSION  
APR 25 1966  
SUNBURY DIVISION  
WICHITA, KANSAS

I certify the above to be true and correct to the best of my knowledge and belief.


DUNNE-GARDNER PETROLEUM, INC.

By

  
Don Gardner

Subscribed and sworn to before me this 21st day of April, 1966.

My Commission Expires:  
November 9, 1969

  
Marilyn E. Fox, Notary Public