

15-051-22979-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Ellis SEC. 8 TWP. 11S RGE. 17W E/W  
 Location as in quarters or footage from lines:  
 NW SW NE


Lease Owner Frontier Oil Co.  
 Lease Name Ganoung Well No. 3  
 Office Address 1720 Kansas St. Bank Bldg., Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 7-8-82  
 Plugging completed 7-8-82  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3422'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	1116'	8 5/8"		Still in hole

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Used pump truck to put fluids in hole.

The following is a list of fluids used, starting with what went in the hole first.

4 sax hulls	-----	approximately 1662' to 1854'
25 sax cement, pozmix 50-50, 4%gel, 3%C.C.	-----	approximately 1534' to 1662'
15 sax gel	-----	approximately 814' to 1534'
70 sax cement, pozmix 50-50-, 4%gel, 3%C.C.	-----	approximately 551' to 814'
5 sax gel	-----	approximately 311' to 551'
1 sax hulls	-----	approximately 263' to 311'
1 8 5/8" plug	-----	approximately 311'
70 sax cement, pozmix 50-50, 4%gel, 3%C.C.	-----	approximately 0' to 263'

Pumped in cement @ 600# maximum pressure, Shut in Pressure @ 100#  
 Pumped down 8 5/8" surface pipe.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Allied Cementing, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

George A. Angle (~~employee of owner~~) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
 1720 Ks St Bldg., Wichita, Ks 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1982



Jean Stocks  
 RECEIVED Notary Public.  
 STATE CORPORATION COMMISSION

My Commission expires: 5-14-85

JUL 22 1982

CONSERVATION DIVISION  
 Wichita, Kansas